

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

MAR 24 2006

Form CP-4
September 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: Scheck Oil Operations
Address: 225 Main St. Russell, Kansas 67665
Phone: (785) 483-1292 Operator License #: 9292
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well to be attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-01885-00-00
Lease Name: Sar Ainsworth Ainsworth, SAM
Well Number: 4 KCC 3-28-06 PKT
Spot Location (QQQQ): _____ SW _____ SE _____ SE
2970 Feet from _____ North / South Section Line
990 Feet from East / _____ West Section Line
Sec. 25 Twp. 18 S. R. 8 _____ East West
County: Rice
Date Well Completed: _____
Plugging Commenced: 3-15-06
Plugging Completed: 3-16-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13"	175'	None
				7"	3135'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

Plugged off bottom with sand to 2720' and 7 sacks cement. Perforated casing @1050', 700' and 225'. Ran 2-3/8" tubing to 1050', pumped 50 sacks cement, pulled up to 700', pumped 50 sacks cement, pulled up to 225' pumped 120 sacks cement, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: Scheck Oil Operations
State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Mike Kelso

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 23rd day of March, 20 06

Irene Herzberg
Notary Public

My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT