

RECEIVED

MAR 29 2006

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: GLM Company
Address: P. O. Box 193
Phone: (785) 483-2123 Operator License #: 3134
Type of Well: Oil Docket #:
The plugging proposal was approved on: 2-27-06
by: Herb Deines (KCC District Agent's Name)
Is ACO-1 filed? [X] Yes [] No
Producing Formation(s): Lansing/KC
Depth to Top: 3816' Bottom: 4025' T.D. 4030'

API Number: 15-065-21,143 -00-00
Lease Name: Nichelson "A"
Well Number: #1
Spot Location (QQQQ): C - SE - SW - NW - NE
990 Feet from [X] North [] South Section Line
1650 Feet from [X] East [] West Section Line
Sec. 14 Twp. 9 S. R. 24 [] East [X] West
County: Graham
Date Well Completed: 7/2/79
Plugging Commenced: 3/1/06
Plugging Completed: 3/1/06

KCC 3-27-06 PKT Per CP 2/3 + Footing map CP-1

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Lansing/KC, Oil and water, 3970', 3976', 8 5/8", 206', . Row 2: 5 1/2", 4029', .

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perforated 2 holes at 2200' and 1035'. Tied to 8 5/8" Casing and mixed 75 sxs. 60/40 Poz, 10% Gel. SIP- 50#.
Tied to 5 1/2" Casing and mixed 40 sxs. 60/40 Poz, 10% Gel and 300# Hulls. Followed with 16 sxs. Gel and then 240 Sxs 60/40 Poz, 10% Gel. Max. Pressure- 400#. SIP- 150#.

Name of Plugging Contractor: Allied Cementing and Acidizing, Inc. License #: 99996
Address: Russell, Kansas

Name of Party Responsible for Plugging Fees: GLM Company
State of _____ County, _____, ss.

Terry W. Piesker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry W. Piesker
(Address) P. O. Box 177, Victoria, Kansas 67671

SUBSCRIBED and SWORN TO before me this 6TH day of MARCH, 20 06
Patricia Dreiling, Notary Public
My Commission Expires: 8.23.06

Notary Public State of Kansas
Patricia Dreiling
My Exp: 8/23/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKM