

RECEIVED

MAR 29 2006

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: GLM Company

Address: P. O. Box 193

Phone: (785) 483-2123 Operator License #: 3134

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2-27-06 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

Lansing/KC Depth to Top: 3810' Bottom: 4010' T.D. 4035'

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15 - 065-21,238 -00 -00

Lease Name: Nichelson "A"

Well Number: #2

Spot Location (QQQQ): - SW - NW - NE

990 Feet from North / South Section Line

2310 Feet from East / West Section Line

Sec. 14 Twp. 9 S. R. 24 East West

County: Graham

Date Well Completed: 5/20/80

Plugging Commenced: 3/1/06

Plugging Completed: 3/1/06

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: Lansing/KC, Oil and water, 3967', 3992', 8 5/8", 206'. Row 2: 5 1/2", 4033'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tied to 5 1/2" Casing and mixed 40 sxs. 60/40 Poz, 10% Gel and 300# Hulls. Followed with 16 sxs. Gel and then 160 Sxs 60/40 Poz, 10% Gel. Pressured to 400#. SIP- 150#. Tied to 8 5/8" Casing and mixed 75 sxs. 60/40 Poz, 10% Gel. SIP- 50#.

Name of Plugging Contractor: Allied Cementing and Acidizing, Inc. License #: 99996

Address: Russell, Kansas

Name of Party Responsible for Plugging Fees: GLM Company

State of County, ss.

Terry W. Plesker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry W Plesker

(Address) P. O. Box 177, Victoria, Kansas 67671

SUBSCRIBED and SWORN TO before me this 6TH day of MARCH, 2006

Patricia Dzielj Notary Public My Commission Expires: 8-23-06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 Notary Public State of Kansas Patricia Dzielj My Appt Exp