

RECEIVED

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

MAR 29 2006

Form CP-4 December 2003

Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

Lease Operator: GLM Company

Address: P. O. Box 193

Phone: (785) 483-2123 Operator License #: 3134

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2-27-06 (Date)

by: Herb Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Lansing/KC Depth to Top: 3822' Bottom: 4025' T.D. 4040'

API Number: 15 - 065-21,726 - 00 - 00

Lease Name: Nichelson "A"

Well Number: #3

Spot Location (QQQQ): - NW - SE - NE

1650 Feet from North / South Section Line

990 Feet from East / West Section Line

Sec. 14 Twp. 9 S. R. 24 East West

County: Graham

Date Well Completed: 12/15/82

Plugging Commenced: 3/1/06

Plugging Completed: 3/1/06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Includes data for Lansing/KC formation and casing sizes.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Well had a Dakota Leak. Perforated 2 holes at 2200'. Ran 2 3/8" Upset Tubing to 2000'. Mixed 65 Sxs. 60/40 Poz, 10% Gel with 300# Hulls and spotted on bottom. Pulled Tubing up to 1100' and mixed 90 sxs. 60/40 Poz, 10% Gel and circulated to surface. Pulled Tubing. Tied to 8 5/8" Casing and mixed 75 Sxs. 60/40 Poz, 10% gel. SIP- 50#. Filled 5 1/2" Casing with 25 sxs. 60/40 Poz, 10% Gel.

Cement stayed at the surface.

Name of Plugging Contractor: Allied Cementing and Acidizing, Inc. License #: 99996

Address: Russell, Kansas

Name of Party Responsible for Plugging Fees: GLM Company

State of _____ County, _____, ss.

Terry W. Piesker (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Terry W. Piesker

(Address) P. O. Box 177, Victoria, Kansas 67671

SUBSCRIBED and SWORN TO before me this 6th day of MARCH, 2006

Notary Public Patricia Drelly My Commission Expires: 8-23-06

Notary Public State of Kansas

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Patricia Drelly My Appt Exp

Handwritten initials