

RECEIVED

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

MAR 29 2006

WELL PLUGGING RECORD KCC WICHITA
K.A.R. 82-3-117

Form CP-4

December 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

Lease Operator: Hummon Corporation

Address: 950 N. Tyler Road, Wichita, KS 67212-3240

Phone: (316) 773-2300 Operator License #: 5050

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/10/2006 (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: 3613 Bottom: 3619 T.D. 3676
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 007-22010 - 60 - 00

Lease Name: Dick

Well Number: 1-6

Spot Location (QQQQ): _____ - C - SW - SE
660 Feet from North / South Section Line

600 Feet from East / West Section Line

Sec. 6 Twp. 32 S. R. 10 East West

County: Barber

Date Well Completed: _____

Plugging Commenced: 3/10/2006

Plugging Completed: 3/14/2006

KCC
3-29-06
PKT
Per
operator
Brent
Rynhar

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	227	None
				5 1/2	3740	2500

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3/10 - MIRU, lay down rods and tubing, set CIBP at 3560', spot 2 sacks cement with dump bailer, rig up tools, stretch pipe

3/14 - stretch and cut pipe at 2500', lay down casing, run 2 3/8" tubing to 600', Allied load hole with 10 sacks gel,

300# hulls, spot 50 sacks 60/40 POZ 6% gel, pull tubing to 240', spot 50 sacks, pull to 40', load to surface, top off 22' sand 2 sacks quick crete

Name of Plugging Contractor: Clarke Corporation License #: 5105


Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Hummon Corporation

State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford

(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 27 day of March, 20 06

Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RAM