

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

WELL PLUGGING RECORD

K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Berexco, Inc.

Address: PO Box 723 Hays, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2-15-06 (Date)

by: Herb Dienes (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

KC Depth to Top: 3781 Bottom: 3930 T.D. 3943  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15-065-20008-00-00

Lease Name: Knoll North S KCC  
PKT  
3-31-06  
CP 2/3

Well Number: S-4

Spot Location (QQQQ): C - NW - SW - \_\_\_\_\_  
1980 Feet from  North /  South Section Line

4620 Feet from  East /  West Section Line

Sec. 29 Twp. 8 S. R. 25  East  West

County: Graham

Date Well Completed: 2-6-67

Plugging Commenced: 2-16-06

Plugging Completed: 2-17-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
KC	OIL, WATER	0	215'	8-5/8	2-1-67	NOT PULLED
		0	3981	5-1/2	2-1-67	NOT PULLED

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tag fish at 3800' pump 100sks 60/40 with 10% gel with hulls. Good returns. Pull tbg to 2400' mix 50 sks 60/40 with hulls 100#  
Pull 20 jts to 1800' circ cement w/ 115 sks. 60/40 with 100# hulls toh with tbg. dug cellar, swedge to 5-1/2 and top with  
20 sks with 50# hulls. 500 psi shut in at 200# hook up to 8-5/8 pump 100 sks 60/40 with 100# hull shut in at 100 psi. Rig down.

Name of Plugging Contractor: Berexco, Inc. License #: 5363

Address: PO Box 723 Hays, KS 67601

Name of Party Responsible for Plugging Fees: Berexco, Inc.

State of Kansas County, Graham, ss.

Mark Leiker (Employee of Operator) or (Operator) on above-described well, first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker

(Address) PO Box 723 Hays, KS 67601

SUBSCRIBED and SWORN to before me this 24 day of February, 2006  
SHANNA MILLER  
NOTARY PUBLIC  
STATE OF KANSAS  
My Commission Expires: 9/19/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
MAR 3 2006  
03-03-06  
KCC WICHITA

Am