

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
MAR 31 2006

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: D. J. Oil Operations
 Address: 305 E 6th St., Ellinwood Ks 67526
 Phone: (620) 564 2759 Operator License #: 31199
 Type of Well: Oil Docket #: N/A
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 10-3-05 (Date)
 by: Case Morris (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
Lansing KC Depth to Top: 3186 Bottom: 3316 T.D. 3349
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-15604-00-00
 Lease Name: Jackson
 Well Number: 1
 Spot Location (QQQQ): NW - NE - NW
330 Feet from North / South Section Line
1050 Feet from East / West Section Line
 Sec. 25 Twp. 20 S. R. 12 East West
 County: Barton
 Date Well Completed: 11-19-48
 Plugging Commenced: 10-28-05
 Plugging Completed: 10-31-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	260	NONE
				5 1/2	3347	NONE

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Perforated at 575' and 1425' Ran tubing to 2000' Pumped 200 sxs 60/40 pozmix - 10% gel cement with 500# hulls. Pulled to 1200'; Circulated with 150 sxs cement and 200# hulls. Pumped 20 sxs cement down casing. Max PSI 500# SIP 400# Pumped 100 sxs cement down backside. Max PSI 150# SIP 150#

Name of Plugging Contractor: Mike's Testing + Salvage, Inc License #: 31529
 Address: P.O. Box 467, Chase, Kansas 67524
 Name of Party Responsible for Plugging Fees: D. J. Oil Operations
 State of Kansas County, Barton, ss.

Rosie Joiner (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Rosie Joiner
 (Address) 305 E 6th, Ellinwood, Ks 67526

SUBSCRIBED and SWORN TO before me this 30th day of March, 20 06
Carol Lenhart My Commission Expires: 3-28-09
 Notary Public



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PJM