

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

MAR 31 2006

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

KCC WICHITA

Lease Operator: Midwestern Exploration Co.

Address: 3500 S. Boulevard, Suite 2B, Edmond, OK 73013

Phone: (405) 340 - 4300 Operator License #: 5263

Type of Well: Oil/Gas Per CP-1 + CP-2/3 Docket #: _____ (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Morrow Perfs Depth to Top: 6254' Bottom: 6264' T.D. _____
Depth to Top: 6290' Bottom: 6296' T.D. _____
Chester Perfs Depth to Top: 6314' Bottom: 6334' T.D. _____

API Number: 15-175-21612-0000

Lease Name: Dunlap

Well Number: 2-8

Spot Location (QQQQ): _____ - C - SW - NW

1980' Feet from North / South Section Line

660' Feet from East / West Section Line

Sec. 8 Twp. 35 S. R. 34 East West

County: Seward

Date Well Completed: 7-2-97

Plugging Commenced: 10-10-05

Plugging Completed: 10-10-05 Per CP-2/3

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 4 1/2, 6855', 1723'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from _____ feet to _____ feet each set.

#1-Pumped 35 sx cement plug from 6050' up to 5500', #2-Pumped 50 sx from 1650' to 1500' well circulated. #3-Pumped 40 sx from 550' up to 450', well circulated. Laid down rest of casing and topped well out w/10 sx of cement from 40' to 4'. Weld on I.D. plate, comer up pits.

Name of Plugging Contractor: Eagle Energy Service License #: 7407

Address: P. O. Box 1661, Liberal, Kansas 67905


Name of Party Responsible for Plugging Fees: Midwestern Exploration Co.

State of Oklahoma County, Oklahoma, ss.

Dale J. Lollar (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) 3500 S. Blvd, Suite 2B, Edmond, OK 73013



SUBSCRIBED and SWORN TO before me this 29th day of March, 20 06
Virginia Means Notary Public My Commission Expires: July 12, 2009