

API NUMBER ¹⁵ -171-20,531-00-01

LEASE NAME Sower (OWWO)

WELL NUMBER 1

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 35 TWP. 16S RGE. 31W COR (W)

COUNTY Scott

Date Well Completed 10/18/05

Plugging Commenced 8:45PM 10/18/05

Plugging Completed 11:00PM 10/18/05

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR WABASH ENERGY CORPORATION

ADDRESS P.O. Box 595 Lawrenceville, IL 62439

PHONE# (618) 943-6451 OPERATORS LICENSE NO. 31251

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Jim Holland (date)

by 10/18/05 (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation None Depth to Top _____ Bottom _____ T.D. 1776

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	341	8 5/8	341	Set in 1998

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

1st Plug @ 1500'w/80sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes w/46 Vis Mud

2nd Plug @ 750'w/40sks 15sks In Rat Hole Plugs displaced with mud.

3rd Plug @ 370'w/50sks Total 205sks 60/40Poz 6%Gel w/1/4#CF/sk By Allied Cementing

4th Plug @ 40'w/10sks Completed @ 11:15PM 10/18/05

Name of Plugging Contractor Discovery Drilling Co., Inc. License No. 31548

Address P.O. Box 763 Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WABASH ENERGY CORPORATION

STATE OF Illinois COUNTY OF Lawrence, ss.


RECEIVED
 MAR 16 2006
 KCC WICHITA

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) P.O. Box 595, Lawrenceville, IL

SUBSCRIBED AND SWORN TO before me this 14th day of March, 2006

[Signature]
 Notary Public



USE ONLY ONE SIDE OF EACH FORM

Pawn