

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC
Address: P.O. Box 372, Hays KS 67601
Phone: (620) 886-5606 Operator License #: 33168
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/21/2006 (Date)
by: Eric macCleren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Open Hole Depth to Top: 4838 Bottom: 4946 T.D. 4946
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 007-22262 - 00-00
Lease Name: Baier
Well Number: #2
Spot Location (QQQQ): _____ - 50'W - SE - SE
660 Feet from North / South Section Line
710 Feet from East / West Section Line
Sec. 31 Twp. 33 S. R. 13 East West
County: Barber
Date Well Completed: 9/18/1989
Plugging Commenced: 2/21/2006
Plugging Completed: 2/23/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	388	None
				4 1/2	4838	2900

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2/21 - Set CIBP at 4750'. 2-22 - spot 2 sacks cement on CIBP with dump bailer, rig up casing tools, stretch and cut pipe at 2900', pull casing
2/23 - run 2 3/8" tubing to 830', Allied load hole with 10 sacks gel, 300# hulls, spot 50 sacks 60/40 poz, 6% gel, pull to 400', spot 50 sacks, pull to 40', load with 15 sacks, operator supervised, top off with 2 yards Redi-mix

Name of Plugging Contractor: Clarke Corporation License # 5150-5105
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC
State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above described well, duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 13 day of March, 2006
Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2006

CONSERVATION DIVISION
WICHITA, KS

PKT