

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC
Address: 125 N. Market, Wichita, KS 67202
Phone: (620) 886-5606 Operator License #: 33168
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/06/2006 (Date)
by: Jerry Stapleton (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 4972 Bottom: 5142 T.D. 5428
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 033-20992-00-00
Lease Name: Boisseau
Well Number: 1/22
Spot Location (QQQQ): N/2 - N/2 - N/2
330 Feet from North / South Section Line
2690 Feet from East / West Section Line
Sec. 22 Twp. 31 S. R. 18 East West
County: Comanche
Date Well Completed: 01/04/1999
Plugging Commenced: 02/08/2006
Plugging Completed: 02/10/2006

KCC 3-20-06 REC CP 2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				10 3/4	340	None
				4 1/2	5505	2500

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


2/8 - Set CIBP at 4940' spot 3 sacks cement with dump bailer, rig up casing tools. 2/9 - stretch and cut pipe at 2500', pull casing to 1000'
2/10 - Allied load hole with 10 sacks gel, pump 75 sacks 60/40 poz, 6% gel, pull pipe to 360, pump 75 sacks cement
pull to 40', load hole with cement, top off with 2 yards Redi-mix cement

Name of Plugging Contractor: Clarke Corporation License #: 5105
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC
State of Kansas County, Barber, ss. John Swinford

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2006
CONSERVATION DIVISION
WICHITA, KS



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 13 day of March, 20 06
Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PPT