

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399, Garden City, KS 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: DH ^{per CP 2/3} _{KCC 3-20-06 per} Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/9/2006 (Date)
by: Jim Holland (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 033-21,372 - 00 - 00
Lease Name: Brass
Well Number: 1-36
Spot Location (QQQQ): E/2 - SW - SW ^{KCC 3-20-06 PKT} _{per 2/3 CP}
525 Feet from North / South Section Line
1150 Feet from East / West Section Line
Sec. 36 Twp. 32 S. R. 16 East West
County: Comanche
Date Well Completed: Spud -9/19/03 (not completed)
Plugging Commenced: 2/13/2006
Plugging Completed: 2/14/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	499	None
				5 1/2	4870	2700


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2/13 - rig up casing tools, stretch and cup pipe at 2700'. 2/14 - pull casing to 850', Allied load hole with 10 sacks gel, pump 50 sacks
60/40 poz, 6% gel, pull pipe to 520', pump 50 sacks, pull pipe to 250', pump 30 sacks, pull to 40', load with 10 sacks
top off 1 3/4 yards Redi-mix

Name of Plugging Contractor: Clarke Corporation License #: 5105
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 13 day of March, 20 06
Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2006

CONSERVATION DIVISION
WICHITA, KS

Room