

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior, Inc.
Address: P.O. Box 399, Garden City, KS 67846
Phone: (620) 275 - 2963 Operator License #: 4058
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 02/14/2006 (Date)
by: Mike Maier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 4735 Bottom: 4740 T.D. 4898
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 033-21,330 - 00 - 00
Lease Name: Brass
Well Number: 2-1
Spot Location (QQQQ): C - S/2 - N/2 - NW
820 Feet from North / South Section Line
1390 Feet from East / West Section Line
Sec. 1-A Twp. 33 S. R. 16 East West
County: Comanche
Date Well Completed: 11/22/2002
Plugging Commenced: 2/14/2006
Plugging Completed: 2/17/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	565	None
				5 1/2	4920	2900

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


2/14 - lay down 70 rods. 2/15 - lay down rods and tubing, set CIBP at 4700', spot 2 sacks cement with dump bailer, rig up casing tools
2/16 - stretch and cut pipe at 2900', pull casing. 2/17 - run 900' of 2 3/8, Allied load hole with 10 sacks gel, 200# hulls
pump 50 sacks 60/40 poz, 6% gel, pull tubing to 580', pump 50 sacks cement, pull to 250', pump 30 sacks, pull 40', load with 10 sacks, top
off with 2 1/4 yards Redi-mix

Name of Plugging Contractor: Clarke Corporation License #: 5150 **5105**
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: American Warrior, Inc.
State of Kansas County, Barber, ss.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2006

John Swinford (Employee of Operator) or (Operator) on above described well, duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is correct, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 13 day of March, 20 06
Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Ram