

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00323-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 23-30S-8W  
2394 feet from S Section Line, 4352 feet from E Section Line  
Lease Name: WEST SPIVEY UNIT Well #: 35  
County: KINGMAN Total Vertical Depth: 4601 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY  
Address: 13727 NOEL RD., STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4594		
SURF	8.625	200		

\$149.53

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/28/2006 10:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Sand to 4200' and 5 sxs; 35 sxs @ 1250'; 35 sxs @ 750'; and circ cmt 250' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/28/2006 2:30 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

Tubing stuck in the hole. Worked tubing loose and pulled. Casing leak at 800'; sanded back and dumped bailed 5 sacks of cement on sand. Recovered casing and pulled from well. Ran tubing to 1250' and spotted 35 sacks of cement. Pulled tubing to 750' and potted 35 sacks of cement. Pulled tubing to 250' and circulated cement to 0'.

60/40 posmix with 4% gel

Allied Cement

**Perfs:**


Top	Bot	Thru	Comments
4259	4284		

**RECEIVED  
KCC DISTRICT #2  
MAR 13 2006  
WICHITA, KS**

INVOICE  
3-21-06  
2006061304

Remarks:  
Plugged through: TBG

District: 02

Signed  (TECHNICIAN)

**RECEIVED  
MAR 20 2006  
KCC WICHITA**