

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22264-00-01
Spot: SWNE Sec/Twnshp/Rge: 19-33S-15W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BRASS Well #: 1-19
County: BARBER Total Vertical Depth: 5378 feet

Operator License No.: 5050
Op Name: HUMMON CORPORATION
Address: 950 N. TYLER
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4550		WITH 2 SX CMT
PROD	5.5	5262	2800	WITH 205 SX CMT \$ 174.79
SURF	8.625	325		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/01/2006 11:45 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4550' WITH 2 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/01/2006 12:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4550' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 660' WITH 400# HULLS MIXED IN WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4780	4786		
4699	4704		
4598	4607		

RECEIVED
MAR 20 2006
KCC WICHITA


INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

DATE: 3-21-06
2006061302

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)