

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-30061-00-00
Spot: W2SENE Sec/Twnshp/Rge: 33-25S-21W
1980 feet from N Section Line, 990 feet from E Section Line
Lease Name: BUTLER TWIN Well #: 4
County: FORD Total Vertical Depth: 4785 feet

Operator License No.: 7864
Op Name: INDIEK, JOHN
Address: RR 1, BOX 62
OFFERLE, KS 67563

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4150		WITH 2 SX CMT
PROD	4.5	4254	0	WITH 100 SX CMT <i>dl 155.51</i>
SURF	8.625	212		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2006 10:40 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: CURTIS KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 659-3470

Proposed Plugging Method: ACCORDING TO STATE REGULATIONS. SET BRIDGE PLUG @ 4150' W/25 SX CMT. ON TOP. PERF @ 600' CIRCULATE CEMENT TO SURFACE UP 8-5/8" MIN. 300 SX IF PULLING PIPE 1000 W/15 SX GEL, 15 SX GEL, 50 SX, 600' W/50 SX 250' W/50 SX, 40' S/105 SX.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2006 12:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

NO CASING RECOVERED: REPEATED ATTEMPTS AT 630' & 590' FAILED. CIBP @ 4150' WITH 2 SX CMT. 1ST PLUG RAN TUBING TO 620' & CIRCULATED CMT TO SURFACE WITH 65 SX CMT. 2ND PLUG MIXED & PUMPED 20 SX CMT DOWN 8 5/8' ANNULUS. HOLE IN SURFACE PIPE. 3/1406: OBSERVED CMT TO TOP OF SURFACE PIPE.

Perfs:

Top	Bot	Thru	Comments
4201	4203		

RECEIVED
MAR 20 2006
KCC WICHITA


Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND ACID.

Plugged through: TBG

INVOICED

3-21-06
2006061303

District: 01



Signed Eric MacLaren
(TECHNICIAN)