

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21087-00-02
Spot: W2W2SW Sec/Twnshp/Rge: 12-32S-12W
1320 feet from S Section Line, 330 feet from W Section Line
Lease Name: DOHERTY Well #: 5
County: BARBER Total Vertical Depth: 4300 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N. MARKET, SUITE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4200		WITH 2 SX CMT
PROD	4.5	4298	3300	WITH 100 SX CMT
SURF	8.625	227		WITH 200 SX CMT

\$139.75

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2006 11:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: JOHN SWINFORD Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4200' & 2 SX CMT. PLUG AT 690' WITH 10 SX GEL & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2006 12:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4200' & PUT 2 SX CMT ON TOP OF CIBP WITH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 690' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4237	4246		
4226	4232		

INVOICED
3-24-06
2006061390

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Stephen J. Pugh
(TECHNICIAN)

RECEIVED

FEB 27 2006

KCC WICHITA

Form CC-202

PKT