

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29358-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 7-26S-18E
865 feet from S Section Line, 3461 feet from E Section Line
Lease Name: NELSON Well #: 06-02
County: ALLEN Total Vertical Depth: 800 feet

Operator License No.: 30638
Op Name: GREER, JOE V. DBA LITTLE JOE'S OIL
Address: PO BOX 162
YATES CENTER, KS 66783

String Size Depth (ft) Pulled (ft) Comment
SURF 7 33

\$ 35.00

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/03/2006 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: JOE GREER Company: GREER, JOE V. Phone: (620) 496-7389

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 800'. THE PLUGGING PROPOSAL WAS TO GELL THE WELL FOR BRIDGING PURPOSES, PLACE A 50' PLUG AT T.D., PLACE A 50' CEMENT PLUG AT 500', AND TO CIRCULATE CEMENT FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/03/2006 10:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE WELL TO 800'. THE WELL WAS GELLED FOR BRIDGING PURPOSES. 20 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 800'. THE 1" PIPE WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

MAR 15 2006 CPT

CHANUTE, KS

RECEIVED
MAR 20 2006
KCC WICHITA

INVOICE

3-21-06
20060001314

Remarks: SPOT LOCATION ESTABLISHED VIA GPS SURVEY.

Plugged through: TBG

District: 03

Signed

Clayton P. Titel
(TECHNICIAN)