

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25091-00-00
Spot: S2NESE Sec/Twnshp/Rge: 19-11S-19W
1590 feet from S Section Line, 610 feet from E Section Line
Lease Name: GREATHOUSE Well #: 6
County: ELLIS Total Vertical Depth: 3650 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3648	0	175 SX CMT
SURF	8.625	215	0	165 SX CMT

118.63
\$

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2006 9:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: MICHAEL A MCGLOCKLIN Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3414

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV at 1396' w/375 sxs. Fluid level 900'.

Plugging Proposal Received By: JAY PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2006 1:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 2500' - mixed and circulated cement with 225 sxs cement with 300# hulls.
POOH. Topped with 35 sxs cement with 200# hulls. S.I.P. 800#.
Hooked up to 8 5/8". S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3572	3575		

RECEIVED
MAR 23 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

INVOICED
3-24-06
2006061392

MAR 20 2006

118

SHIELDS OIL PRODUCERS
 RUSSELL KS 67665

19-11S-19W
 1590' FSL & 610' FEL, SEC

#6 GREATHOUSE

site 5 N & 3-3/4 W OF HYACINTH KS
 contr: SHIELDS DRILLING #1
 geol: RANDALL KILIAN

city: ELLIS
 field: PHOENIX

API 15-051-25091

fr date 05/22/2001
 spd date 06/12/2001
 drlg comp 06/20/2001
 card issued 09/03/2001
 last revised 09/03/2001

ELV: 2006 KB, 2001 GL LOG

tops.....	depth/datum
ANH.....	1367 +639
B/ANH.....	1406 +600
TOP.....	3005 -999
HEEB.....	3223 -1217
TOR.....	3243 -1237
LANS.....	3262 -1256
*LANS B.....	3280 -1274
*LANS C.....	3296 -1290
*LANS D.....	3314 -1308
*LANS E.....	3334 -1328
*LANS F.....	3344 -1338
*LANS G.....	3356 -1350
*LANS H.....	3402 -1396

IP status

OIL, P 40 BOPD, NW, ARB 3572-3575, 07/12/2001

*LANS I.....	3420 -1414
*LANS J.....	3438 -1432
*LANS K.....	3452 -1446
*LANS L.....	3476 -1470
BKC.....	3488 -1482
SMP DOL.....	3555 -1549
ARB.....	3568 -1562
PBTD.....	3614 -1608
LTD.....	3649 -1643
RTD.....	3650 -1644
*SAMPLE TOP	

CSG: 8-5/8" 215 / 165 SX (ALT 2), 5-1/2" 3648 / 175 SX, DV
 TOOL AT 1396 / 375 SX

COPYRIGHT 2001
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)