

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-21394-00-00  
Spot: SENESE Sec/Twnshp/Rge: 4-14S-17W  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease Name: PETE Well #: 1  
County: ELLIS Total Vertical Depth: 3598 feet

Operator License No.: 5252  
Op Name: NIXON, R P OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3588	0	w/unknown sxs cmt
SURF	8.625	206	0	w/unknown sxs

116.94

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/21/2001 1:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: DUANE ACTERBERG Company: NIXON, R P OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Squeezed at 851' - 884' w/150 sxs.  
Hole in casing at 720'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/21/2006 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 1225' and 1850'.  
TIH with tubing to 2200' - mixed and circulated up 4 1/2" with 110 sxs cement and 300# hulls.  
Pumped 25 sxs cement and circulated up 8 5/8" - shut in  
POOH. Swaged onto 4 1/2" and pumped 65 sxs cement with 200# hulls.  
Max. P.S.I. 700#. S.I.P. 600#.

Perfs:

RECEIVED  
MAR 27 2006  
KCC WICHITA

INVOICED  
3-27-06  
2006061403

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

110

Signed Jay Pfeifer  
(TECHNICIAN)

MAR 22 2006

PKT

R.P. NIXON OPERATIONS  
207 W. 12TH

#1 PETE

4-14-17W  
SE NE SE

HAYS, KS.

CONTR BERGMAN DRLLG. CO.

CTY ELLIS

GEOL

FIELD TOULON

2002 KB CM 10/24/77 CARD ISSUED 1/19/78 IP P 25 BOPD + 30% W  
LKC 3308-10, 3353-55 & 3372-74

+	+	+
+	+	+
+	+	+

API 15-051-21,394

LOG	TOPS	DEPTH	DATUM
ANH	1196	+ 806	
TOP	3018	-1016	
HEEB	3238	-1236	
TOR	3259	-1257	
LKC	3284	-1282	
BKC	3509	-1507	
GONG	3520	-1518	
RTD	3598	-1596	

8-5/8" 206, 4 1/2" 3588  
DST (1) 3308-77/30-30-30, GTS/45"  
500' GSY FROTHY OIL, 240' OILY  
WTR, SIP 852-827#, FP 349-439#  
MCT - PF 1/3373, 1/3353, 1/3309, AC  
2000, RE-PF 3372-3374, 3353-3355,  
3308-10, REC LD, POP, SWB 15 BFPH,  
80% OIL

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS