

TQ:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-19470-00-00
Spot: NESENW Sec/Twnshp/Rge: 12-22S-10E
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: DEMALORIE-SOWDER Well #: 52
County: GREENWOOD Total Vertical Depth: 2158 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 510 HARDAGE CENTER 100 S. MAIN
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.625	2066	1201	
SURF	8.625	1700		

\$ 70.14

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2006 8:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Rcvd. from: _____ Company: R.R.A., INC. Phone: (316) 262-3411

Proposed Plugging Method: 50' CEMENT PLUG AT 2000', 50' CEMENT PLUG AT 1000', 150' CEMENT PLUG TO SURFACE.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2006 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

PLUGGED BACK TO 2000' WITH SAND, DUMPED 12 SACKS CEMENT WITH DUMP BALER, SHOT 6 5/8" CASING AT 1201', PULLED CASING OUT, SHOT 8 5/8" CASING AT 1000', 504', PULLED CASING OUT. RAN TUBING TO 1000', PUMPED 35 SACKS CEMENT, PULLED TUBING TO 130', PUMPED 60 SACKS CEMENT, PULLED TUBING TO 75', PUMPED 75 SACKS CEMENT TO SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

MAR 22 2006 *BL*

CHANUTE, KS

Remarks: WELL DRILLED 2/13/1926.

Plugged through: TBG

District: 03

Signed

Mike Heffern by BL
(TECHNICIAN)

INVOICED

3-27-06

2006061295

RECEIVED
MAR 27 2006
KCC WICHITA

BLT