

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-24017-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 26-34S-11E  
3000 feet from S Section Line, 4785 feet from E Section Line  
Lease Name: RILEY (BOWMAN) Well #: 30  
County: CHAUTAUQUA Total Vertical Depth: 1800 feet

Operator License No.: 30522  
Op Name: CORNWELL, LTD.  
Address: PO BOX 142  
GRENOLA, KS 67346

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5	1800	0	
SURF	7	40	0	

\$ 58.50

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2005 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.  
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO RUN 1" TO TD & PUMP FULL OF GEL & CEMENT.

Plugging Proposal Received By: RON ROWE Witness Type: NONE  
Date/Time Plugging Completed: 12/27/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" HYDRIL INSIDE 5" TO 1800'(TD), GELLED HOLE, & PUMPED 15 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" UP TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" OUT & TOPPED-OFF WELL. USED TOTAL OF 55 SACKS CEMENT & 3 SACKS GEL.

Perfs:

RECEIVED  
KCC DISTRICT #3

FEB 17 2006

CHANUTE, KS

RR

INVOICED

3-27-06

200.6061397

Remarks: PLUGGED OLD OIL WELL.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED  
MAR 27 2006  
KCC WICHITA

PKT