

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-30664-00-01
Spot: NWSENE Sec/Twnshp/Rge: 23-15S-18W
3630 feet from S Section Line, 990 feet from E Section Line
Lease Name: GROSS Well #: 1
County: ELLIS Total Vertical Depth: 3758 feet

Operator License No.: 32875
Op Name: CWB - CO, A GENERAL PARTNERSHIP
Address: 40837 BEAR CREEK ROAD
SPRINGVILLE, CA 93265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3513	0	w/85 sxs cmt
SURF	8.625	895	0	w/400 sxs cmt

\$11,122.14

Well Type: SWD UIC Docket No: D18730.0 Date/Time to Plug: 03/21/2006 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE
Proposal Rcvd. from: JAMES HERTLE Company: CWB - CO, A GENERAL PARTNERS Phone: (785) 650-3118

Proposed Plugging Method: Ordered out 475 sxs 60/40 pozmix - 10% gel - 1200# hulls.
Run tubing to 2000'. Pump cement and hulls unit it circulates out of 5 1/2" production casing. Tie onto 5 1/2" casing and pump cement until a positive shut in pressure is achieved and maintained. Tie onto 8 5/8" annulus and pump cement until a positive shut in pressure is achieved and maintained.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/21/2006 12:00 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

Ran 70 joints of tubing in the hole to an approximate depth of 2000'.
Pumped 140 sxs cement with 600# hulls - hole circulated during the entire time.
Pulled 35 joints of tubing to approximately 1000'.
Pumped 80 sxs cement with 600# hulls - hole circulated cement colored water which cleared up during the first 40 sxs cement pumped.
Circulated good cement at end of the 80 sack plug.
Tied onto the 5 1/2" production casing and pumped 10 sxs cement. S.I.P. 250#.
Tied onto 8 5/8" annulus and attempted to pumped into it. Pressure at 300#.
Plug down at 12:00 noon.

Perfs:

RECEIVED
MAR 27 2006
KCC WICHITA

INVOICED

DATE 3-27-06
WEL. NO. 2006061398

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Handwritten initials


Signed

Signature of Bruce D. Basye
(TECHNICIAN)

MAR 22 2006

Handwritten initials

9-72 MAP NO REPL. COMP. SEC. 23-15S-18W
 STATE Kans COUNTY Ellis LOC. NW SE NE
 OPER John C. Graves et al - Wichita, Ks. FT/FR _____ LINE _____
 WELL F FARM Cross FT/FR _____ LINE _____
 POOL Leiker SF ELEV. 1955 GR. 1957 OF 1960 KB _____
 CONT. Co. tools GEOL. Carl Becker
 CO. INT _____
 FR 6-12-64 SPUD 6-12-64 COMP. 9-8-64
 TD 3540 FM Arb PBTD _____
 COMP. RECORD Arb 3513-40 OH natural
Co P 25 BOPD
8 5/8" @890 w/400 sx. 5 1/2" @3513 w/85 sx. *Data Inc.*



(KE Sp1)		DSI #1 (Lans) 3254-86 Op 1 hr WB R 60"
Top	2921 - 961	WM w/oil spks. ISIP 864#/30" IFP 34# FFP
Hb	3204 - 1244	54# FSIP 514#/30", RID 3540, 5 1/2" @3513
Top	3226 - 1266	w/85 sx., No OH Log, CO 3540 TD, FI 1000
Lans	3250 - 1290	/1 1/2 hrs, FI 1800' oil-NW/8 hrs, POP, nat.
Arb	3529 - 1569	Co P 25 BOPD, Arb 3513-40 - COMPLETED
RID	3540 - 1580	(8-31-64)
DDTD	3758	REPLACEMENT COMPLETION (5-13-65)
Replaced to correct spot - Was N/2 S/2 NE. Is NW SE NE		