

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: D.R. Lauck Oil Company, Inc.
Address: P.O. Box 488/122 N. Main, Ellinwood, Ks. 67526
Phone: (620) 564-2013 Operator License #: 5427
Type of Well: SWD Oil (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) Docket #: D-14696
(If SWD or ENHR)
The plugging proposal was approved on: March 1, 2006 (Date)
by: Wayne Kocher (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Depth to Top: 4440' Bottom: 4553' T.D. 4553'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 095-20118-00-00
Lease Name: Bradshaw
Well Number: #1
Spot Location (QQQQ): _____ - NW - NE - SE
2310' Feet from North / South Section Line
990' Feet from East / West Section Line
Sec. 5 Twp. 27 S. R. 9 East West
County: Kingman
Date Well Completed: 10/28/1968
Plugging Commenced: 03/07/06
Plugging Completed: 03/08/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface	0'	237'	10-3/4"	237'	0'
	Production	0'	4440'	7"	4440'	1500'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Sand off bottom to 4440' with 5 sacks cement. Cut ring off casing head. Set in jacks. Tried to pull slips out of head - wouldn't come.
Pulled casing slips out of head - rigged up log truck. Trip in hole with shot. Shot off casing at 1740'. Pulled 7-1/2" casing. Left 9 joints in well. Plugged well at 1400' with 50 sacks cement. 300' to surface with 150 sacks. Loaded up jacks, rigged down and moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901
Address: P.O. Box 231, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: D.R. Lauck Oil Company, Inc.

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct as help me, Fed.

KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

Edward S. Nemnich
(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 13th day of March, 20 06

Karen J. Mitchell My Commission Expires: 4/13/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2006
CONSERVATION DIVISION
WICHITA, KS

Don