

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Deutsch Oil Company
Address: 8100 E. 22nd Street N. Bldg 600#-D, Wichita, KS. 67226
Phone: (316) 681-3567 Operator License #: 3180
Type of Well: Gas Well Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: March 8th, 2006 (Date)
by: Richard Lacey (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 2032' Bottom: 2119' T.D. 4038'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 145-202350001
Lease Name: Blackwell
Well Number: #1-26
Spot Location (QQQQ): _____ - SW - SW - SE
330' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 26 Twp. 22 S. R. 16 East West
County: Pawnee
Date Well Completed: 11/26/1971
Plugging Commenced: 03/09/06
Plugging Completed: 03/13/06

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|------------|--|-------|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | Surface | 0' | 235' | 8-5/8" | 235' | 0' |
| | Production | 0' | 4037' | 4-1/2" | 4037' | 0' |
| | | | | | | |
| | | | | | | |

RECEIVED
MAR 16 2006
KCC WICHITA


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

M.I.R.U. Sand off bottom to 1950' with 4 sacks cement. Set casing jacks over well. Pulled slips out of casing head. Got new plugging orders from state. Pulled jacks off well. Loaded jacks - got casing ready to plug. Rigged up Log-Tech - perforated 4-1/2" casing at 1025'. Pumped 80 sacks cement. Let set 1 hour. Trip back in with shot and perforated at 250'. Pumped 195 sacks cement - circulated to surface. Mixed 25 more sacks and pressured up to 600# - shut well in. Rigged down and moved off.

Name of Plugging Contractor: D.S. & W. Well Servicing, Inc License #: 6901
Address: P.O. Box 231, Claflin, Kansas 67525
Name of Party Responsible for Plugging Fees: Deutsch Oil Company

State of Kansas County, Barton, ss.

Edward S. Nemnich (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


KAREN J. MITCHELL
Notary Public - State of Kansas
My Appt. Expires 4/13/06

(Signature) Edward S. Nemnich

(Address) P.O. Box 231, Claflin, Kansas 67525

SUBSCRIBED and SWORN TO before me this 14th day of March, 20 06

Karen J. Mitchell
Notary Public

My Commission Expires: 4/13/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

127