

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117**

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: DOWNING-NELSON OIL CO., INC.
 Address: P.O. Box 372 Hays, KS 67601
 Phone: (785) 621 - 2610 Operator License #: 30717
 Type of Well: D & A Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 1/15/06 (Date)
 by: Herb Deines (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 195-22,314-00-00
 Lease Name: SCHOENTHALER
 Well Number: 1-11
 Spot Location (QQQQ): G - E/2 - E/2 - NW
1210 Feet from North / South Section Line
2170 Feet from East / West Section Line
 Sec. 11 Twp. 14 S. R. 21W East West
 County: TREGO
 Date Well Completed: 1/16/06
 Plugging Commenced: 12:00PM 1/16/06
 Plugging Completed: 3:30PM 1/16/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	222	8 5/8	222	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


1st Plug @ 4000' W/25sks 5th Plug @ 40'W/10sks-Circulated 1st Plug 15 Minutes W/55Vis Mud
2nd Plug @ 1650'W/25sks Plugs Displaced with Mud
3rd Plug @ 875' W/100sks Total 215sks 60/40Poz 6%Gel W/1/4#CF/sk By Allied Cementing
4th Plug @ 275' W/40sks Completed @ 3:30PM 1/16/06

Name of Plugging Contractor: Discovery Drilling Co., Inc. License #: 31548
 Address: P.O. Box 763 Hays, KS 67601
 Name of Party Responsible for Plugging Fees: DOWNING-NELSON OIL CO., INC.

State of KS County, Ellis, ss.
Alan Downing (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Alan Downing
 (Address) PO Box 372, Hays KS 67601

SUBSCRIBED and SWORN TO before me this 21 day of March, 20 06
Michelle L Meier My Commission Expires: 7/28/09
 Notary Public



KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
 MAR 22 2006
 KCC WICHITA

Pam