

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

MAR 23 2006

KCC WICHITA

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hummon Corporation

Address: 950 N. Tyler Road, Wichita, KS 67212-3240

Phone: (316) 773-2300 Operator License #: 5050

Type of Well: Oil KCC 3-24-06 PCT Perc CP 2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 3/1/2006 (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: <u>5147</u>	Bottom: <u>5220</u>	T.D. <u>5340</u>
Depth to Top: <u>4958</u>	Bottom: <u>4964</u>	T.D. _____
Depth to Top: <u>4765</u>	Bottom: <u>4770</u>	T.D. <u>4900</u>

API Number: 15 - 033-21366-0000

Lease Name: Merrill Trust

Well Number: 1-25

Spot Location (QQQQ): _____ - NW - NE - NE

380 Feet from ☒ North / ☐ South Section Line

975 Feet from ☒ East / ☐ West Section Line

Sec. 25 Twp. 33 S. R. 16 ☐ East ☒ West

County: Comanche

Date Well Completed: _____

Plugging Commenced: 3/1/2006

Plugging Completed: 3/6/2006

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				13 3/8	318	None
				5 1/2	5340	700

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3/1 - Lay down tubing. 3/2 - Finish laying down tubing, set CIBP at 4700', spot 2 sacks cement with dump bailer, swab oil out of casing

rig up tools, stretch and cut pipe at 800'. 3/3 - cut pipe at 700', lay down casing. 3/6 - run tubing to 748', Allied

load hole 15 sacks gel, 200# hulls, spot 50 sacks 60/40 POZ, 6% gel, 200# hulls, pull to 350', spot 80 sacks, pull to 40', load hole with

30 sacks, top off 1/2 yard redimix

Name of Plugging Contractor: Clarke Corporation License #: 5105


Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Hummon Corporation

State of Kansas County, Barber, ss.

John Swinford

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 20 day of March, 20 06

Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pam