

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: ZU LLC
Address: 108 West 34th, Hays, Kansas 67601
Phone: (785) 625-6588 Operator License #: 32699
Type of Well: ENHR Docket #: E-12893
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: January 23rd, 2006 (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Misner Depth to Top: 3703 Bottom: 3704 T.D. _____
Viola Depth to Top: 3735 Bottom: 3743 T.D. 3818

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 185-22340-00-01
Lease Name: Zenith Unit waterflood Unit
Well Number: ZU#35
Spot Location (QQQQ): _____ - _____ - _____ - S2
1320 Feet from North / South Section Line
2640 Feet from East / West Section Line
Sec. 1 Twp. 24 S. R. 11 East West
County: Stafford
Date Well Completed: 1/16/1986 (original)
Plugging Commenced: 1-25-2006
Plugging Completed: 1-25-2006

KCC 3-24-06
PKT
per CP-2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Misner	Oil - 4'	0	212	8 5/8"	212	0
Viola	Oil - 10'	0	3717	5 1/2"	3717 3817	0
		0	3700	3 1/2"	3700	0

KCC PKT 3-24-06
Per CP2/3 & CP1.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 2 1/16" tubing to 3576'. Spotted 40 sacks common 3% CC on bottom. Pulled tubing. Waited one hour. Hooked on to 3 1/2" tubing.
Pressured up tubing to 200 PSI. Held Pressure. Log Tech perforated casing at 550' W/ 2 SPF. Hooked onto 3 1/2" casing and mixed 50 sacks of 60/40 with 6% gel and circulated cement to surface in 5 1/2" casing. Hooked on to 8 5/8" surface casing. Mixed 85 sacks of 60/40 with 6% gel and pumped all of the 85 sacks in, cement was at surface and the pressure was 500 PSI. Shut in @ 400 PSI.

Name of Plugging Contractor: Klima Well Service Co. License #: 7023

Address: 610 West Front, Claflin, Kansas 67525

Name of Party Responsible for Plugging Fees: ZU LLC

State of Kansas County, Ellis, ss.

Greg Whitehair (Employee of Operator) or (Operator) on above-described well, being first duty

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

NOTARY PUBLIC - State of Kansas
MAURICE J. PFEIFER
My Appt. Exp. _____

(Signature) Greg Whitehair
(Address) 108 West 34th, Hays Kansas 67601

SUBSCRIBED and SWORN TO before me this 21 day of March, 2006

Maurice Pfeifer My Commission Expires: 5-13-07
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAR 23 2006

KCC WICHITA

PAM