

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
MAR 23 2006
KCC WICHITA
230100-00
KCC 3-21-06 PKT PER CP 213

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
blanks must be Filled

Lease Operator: Woolsey Operating Company, LLC
Address: 125 N. Market, Wichita, KS 67202
Phone: (620) 886-5606 Operator License #: 33168
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 2/23/2006 (Date)
by: Eric Mac Cleren (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: 4720 Bottom: 4765 T.D. 4981
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-04006
Lease Name: Meyer
Well Number: B-4
Spot Location (QQQQ): _____ - S/2 - SW - NE
2310 Feet from North / South Section Line
1980 Feet from East / West Section Line
Sec. 20 Twp. 34 S. R. 13 East West
County: Barber
Date Well Completed: 3/28/1990
Plugging Commenced: 2/23/2006
Plugging Completed: 2/27/2006

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	400	None
				4 1/2	5036	2700

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
2/23 - Lay down rods, lay down 60 joints of 2 3/8. 2/24 - lay down tubing, set CIBP at 4630', dump 2 sacks cement with dump bailer
rig up casing tools, stretch and cut pipe at 2700', lay down casing, 2/27 - run tubing, stack out 770', pull to 750'
Allied load hole with 12 sacks gel, 400# hulls, spot 50 sacks 60/40 POZ 6% gel, pull to 430', spot 50 sacks, pull to 40', load 15 sacks

Name of Plugging Contractor: Clarke Corporation License #: 5105
Address: P.O. Box 187, Medicine Lodge, KS 67104

Name of Party Responsible for Plugging Fees: Woolsey Operating Company, LLC
State of Kansas County, Barber, ss.

John Swinford (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) John Swinford
(Address) P.O. Box 187, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 20 day of March, 20 06
Glenda Morrison My Commission Expires: 11/30/06
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202