

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED

Form CP-4

September 2003

Type or Print on this Form

Form must be Signed

All blanks must be Filled

MAR 24 2006

KCC WICHITA

Lease Operator: John Indiek

Address: 10545 Rd, 134 Offerle, Ks. 67563

Phone: (620 659 3470) Operator License #: 7864

Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Steve Durant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: Bottom: T.D. (repeated three times)

API Number: 15-057-30060-00-00

Lease Name: Butler A KCC 3-27-06 per CPA/3

Well Number: 1-A-1

Spot Location (QQQQ): C SW NE

1980 Feet from X North / South Section Line

1980 Feet from X East / West Section Line

Sec. 33 Twp. 25 S. R. 21 East X West

County: Ford

Date Well Completed: 6-29-66

Plugging Commenced: 3-8-06

Plugging Completed: 3-9-06

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing sizes 8-5/8" and 4-1/2" with depths 250' and 4778'.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Plugged off bottom with sand to 4130' and 4 sacks cement. Ran 2-3/8" tubing to 600', purped 70 sacks cement and circulated to surface, layed down tubing, tied onto surface, purped 130 sacks cement, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529

Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: John Indiek

State of Kansas County, Rice ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 23rd day of March, 2006

[Handwritten Signature] My Commission Expires



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PAM