

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20981-00-00  
Spot: NENWNE Sec/Twnshp/Rge: 2-30S-9W  
4964 feet from S Section Line, 1772 feet from E Section Line  
Lease Name: WHITMER Well #: 1  
County: KINGMAN Total Vertical Depth: 4203 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N. MARKET, STE 1130  
WICHITA, KS 67202

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 4.5   | 4202       |             | 200 sx  |
| SURF   | 8.625 | 323        |             | 275 sx  |

60  
#136

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2006 1:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Perfs @ 4148' - 4156'; sand back to 4090'; cap w/ 4 sxs; 35 sxs @ 1400'; 35 sxs @ 900'; and circ cmt 380' - 0'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 02/17/2006 3:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand from TD to 4090' and capped with 4 sacks of cement. Recovered casing from 2721' and pulled to 1400' where 35 sacks of cement were spotted. Did not load hole; first plug did not circulate. Casing pulled to 900'; loaded hole. Spotted 35 sacks of cement and pulled casing to 380' where cement was circulated to surface.

Copeland  
60/40 posmix with 4% gel

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4148 | 4156 |      |          |

**RECEIVED  
KCC DISTRICT #2  
FEB 28 2006  
WICHITA, KS**

**RECEIVED  
MAR 14 2006  
KCC WICHITA**

Remarks:  
Plugged through: CSG

District: 02

Signed [Signature]  
(TECHNICIAN)

**INVOICED**  
DATE 3-14-06  
INV. NO. 2006061277

ra