

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-20644-00-01
Spot: NENENW Sec/Twnshp/Rge: 32-19S-10W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: CROSS REACH FARMS Well #: 2
County: RICE Total Vertical Depth: 1489 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 216
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|------|------------|-------------|------------|
| PROD | 4.5 | 1489 | | 50 SX CMT |
| SURF | 7 | 247 | | 175 SX CMT |

48³⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/06/2006 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Sand off perf to 1389' and cap with 4 sxs cmt. Pull pipe to 800' and pump 35 sxs. Pull pipe to 300' and circ to surf.

Plugging Proposal Received By: GREG EVES WitnessType: NONE
Date/Time Plugging Completed: 02/06/2006 2:30 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded perforations to 1389' and capped with 4 sacks of cement. Cut pipe; pulled to 800'; and pumped 35 sacks of cement. Pulled pipe to 300'; pumped 120 sacks of cement; and circulated to surface.

60/40 posmix with 4% gel

Copeland Cement #030250

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 1439 | 1443 | | |

RECEIVED
KCC DISTRICT #2
FEB 14 2006
WICHITA, KS

RECEIVED
MAR 14 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)

INVOICED
DATE 3-14-06
INV. NO. 2006061280

a