

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20127-00-01
Spot: SWSWSW Sec/Twnshp/Rge: 16-14S-10W
338 feet from S Section Line, 5141 feet from E Section Line
Lease Name: A SOUKUP Well #: 1
County: ELLSWORTH Total Vertical Depth: 3210 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 SOUTH MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2975		275 SX CMT
SURF	8.625	253		165 SX CMT

#104 33

Well Type: EOR UIC Docket No: E16442.1 Date/Time to Plug: 01/16/2006 8:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: FRANK BIEKER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Sand perms to 2785' & cap w/ 4 sxs. Perf @ 1250', 900' & 305'. 35 sxs @ 1250'; 35 sxs @ 900'; circ from 305' to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 01/16/2006 5:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded to 2000' and capped with 4 sacks of cement. Perforated pipe at 1250', 900', and 305'. Pumped 35 sacks of cement at 1250' and 900'. Pumped 40 sacks of cement at 305' to fill to surface. Pumped 65 sacks of cement in surface casing to fill to surface. Top plug dropped to 110'. Ellsworth Redi Mix brought 2 yds slurry mix to bring plug to surface.

175 sacks of 60/40 posmix with 4% gel

Allied Cement #18724
Ellsworth Redi Mix #37861

Perfs:

Top	Bot	Thru	Comments
2836	2849		
2452	2456		

RECEIVED
KCC DISTRICT #2
MAR - 7 2006
WICHITA, KS

RECEIVED
MAR 14 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

INVOICED
DATE 3-14-06
2006061284

DL