

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21949-00-01
Spot: SWNESW Sec/Twnshp/Rge: 14-29S-11W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HISKETT Well #: 3-14
County: PRATT Total Vertical Depth: 4749 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4749	3820	WITH 150 SX CMT
SURF	8.625	264		WITH 200 SX CMT

#154³⁴

Well Type: EOR UIC Docket No: E25992.1 Date/Time to Plug: 02/22/2006 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY BAIRD Company: F.G. HOLL Phone: (316) 684-8481

Proposed Plugging Method: SAND TO 4275' & 5 SX CMT. PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/22/2006 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4275' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 700' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4649			
4648	4651		
4647			
4646			
4326	4354		

INVOICED
DATE 2-28-06
INV. NO. 2006061195

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
FEB 27 2006
KCC WICHITA

Form SP-2/3