

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01618-00-00
Spot: SENWNW Sec/Twnshp/Rge: 10-9S-19W
4290 feet from S Section Line, 4290 feet from E Section Line
Lease Name: ROSTICAL C Well #: 4
County: ROOKS Total Vertical Depth: 3443 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3440	0	w/150 sxs cmt
SURF	8.625	310	0	w/175 sxs cmt

111 90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2006 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed Plugging Method: Ordered out 200 sxs Swift Multi-Density Cement with 500# hulls.
High fluid level.
Old squeeze 1978 - 830'-1027'; 1979 - 1767'-1799' and 2020'-2025'.
CIBP at 3210'. Arbuckle open hole 3440.5' to 3443.5'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/08/2006 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Unable to get below 895' - out of 5 1/2" casing.
Ran tubing to 875'. Swift pumped 25 sxs Swift Multi-Density Cement.
Pulled tubing to 837' and pumped 75 sxs SMD - circulated cement.
PTOH. Squeezed down 5 1/2" casing w/50 sxs - circulated cement out 8 5/8".
Shut in and squeezed 10 sxs SMD.
Max. P.S.I. 425#. S.I.P. 425#.

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 15 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

110 INVOICED

DATE 3-15-06

INV NO 2006061288

Form CP-2/3

MAR 10 2006