

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22035-00-01
Spot: NWNE Sec/Twnshp/Rge: 31-29S-13W
4464 feet from S Section Line, 1874 feet from E Section Line
Lease Name: DORIS LAMBERT A Well #: 1-31
County: PRATT Total Vertical Depth: 4800 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4300		
CIBP		4540		
PROD	4.5	4789	3020	WITH 225 SX CMT #156 ⁶⁰
SURF	13.38	280		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/21/2006 8:45 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TERRY BAIRD Company: F.G. HOLL Phone: (316) 684-8481

Proposed Plugging Method: SAND BACK TO 3950' & 4 SX CMT. PLUG A T785' WITH 12 SX GEL & 50 SX CMT. PLUG A 310' WITH 100 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2006 10:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3960' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 785' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.


Perfs:

Top	Bot	Thru	Comments
4311	4318		
4013	4015		

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
FEB 27 2006
KCC WICHITA

Form CR 2/3

INVOICED
DATE 2-28-06
NO. 2006061195