

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-05293-00-01
Spot: SWSENE Sec/Twnshp/Rge: 27-14S-19W
2970 feet from S Section Line, 1065 feet from E Section Line
Lease Name: KRAUS A Well #: 1
County: ELLIS Total Vertical Depth: 3731 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE ROAD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	615	0	w/unknown sxs cmt
SURF	8.625	1380	0	w/800 sxs cmt

#121²⁶

Well Type: SWD UIC Docket No: D06904.0 Date/Time to Plug: 03/06/2006 9:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 10% gel.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2006 12:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Swaged onto 5 1/2" - tried to get an injection rate - could not pump into.
Hooked up to 8 5/8" - instant 300#.
TIH with tubing to 1350' - mixed and circulated cement up 5 1/2" with 150 sxs cement.
POOH. Hole full of cement.

RECEIVED
MAR 13 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Jay Pfeifer (TECHNICIAN)

MAR 08 2006

INVOICED
DATE 3-13-06
2006061271

15-051-02895-00-00
 TROJAN OIL COMPANY #1 KRAUS A 75W of SW SE NE 27-14-19W

Contr. _____ ELLIS _____ County _____
 E 2086 Comm. 12-30-47 Comp. 4-16-48 IP 50 EOPD

Tops	Depth	Datum
ANH	1355	+731
LANS	3408	-1322
ARB	3715	-1629
REAGAN	3727	-1641.8
T.D.	3731	

Casing 8 5/8 1364 in 600 ft
 9 1/2 3747 in 150 ft
 Drills Report
 8" 1336 SHOT 10 QTS, 3726-31
 5" 3725 SWB 5 FOPH/2 1/4 HRS
 SWB 42 BO/6 HRS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

