

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19061-00-00
Spot: SWNENW Sec/Twnshp/Rge: 8-19S-10W
4514 feet from S Section Line, 3752 feet from E Section Line
Lease Name: STOLTZ Well #: 5
County: RICE Total Vertical Depth: 3342 feet

Operator License No.: 31070
Op Name: EAGLE RIVER ENERGY CORPORATIO
Address: 7060 S. YALE #609
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3336		100 SX CMT
SURF	8.625	252		190 SX CMT

108⁶²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2006 11:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Revd. from: GEORGE RICE Company: EAGLE RIVER ENERGY CORPORA Phone: (620) 793-2645

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 02/23/2006 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2800' and pumped 35 sacks of cement through tubing. Perforated at 1250', 950', and 260'. Ran tubing to 1250' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled tubing to 950' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled tubing to 300' and circulated cement to surface. Topped off with 10 sacks of cement.

Copeland #C-030276

215 sxs -- 60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3334	3342		
3002	3290		

RECEIVED
KCC DISTRICT #2

FEB 28 2006

WICHITA, KS

RECEIVED
MAR 14 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 3-14-06

INV NO 2006061274