

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21509-00-00
Spot: SENWSE Sec/Twnshp/Rge: 5-21S-6W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: ENGELLAND Well #: 1
County: RICE Total Vertical Depth: 3524 feet

Operator License No.: 8917
Op Name: GUSTUS, DEAN DBA JD PRODUCTION
Address: 701 MAIN
GENESEO, KS 67444

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3524	2610	
SURF	8.625	206		

114⁵³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2005 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method:

See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/18/2005 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded to 3385' and put 4 sacks of cement on top. Cut off casing at 2610'. Pulled casing to 1000' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 600' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 260' and circulated cement to surface.

60/40 posmix with 4% gel

United Cement #6472

Perfs:

RECEIVED
KCC DISTRICT #2
FEB 28 2006
WICHITA, KS

RECEIVED
MAR 14 2006
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED
DATE 3-14-06
INV. NO. 2006061279