

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-00442-00-00  
Spot: NENESW Sec/Twnshp/Rge: 9-10S-23W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: HOOF Well #: 1  
County: GRAHAM Total Vertical Depth: 3955 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 8100 E. 22ND N. BLDG. 300  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3955	0	w/unknown sxs cmt
SURF	8.625	217	0	w/unknown sxs cmt

\$ 128.54

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/13/2006 10:00 AM  
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE  
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 10 sxs gel spacer - 500# hulls.  
Well squeezed at 1527' -1612' w/205 sxs; 1689' w/90 sxs.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/13/2006 3:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

TIH with tubing to 3850' - mixed and spotted 60 sxs cement with 500# hulls.  
Pulled up to 3050' - spotted 10 sxs gel.  
Pulled up to 2000' - circulated cement with 140 sxs cement with 100# hulls.  
POOH. Swaged onto 5 1/2" and pumped 25 sxs. S.I.P. 500#.  
Hooked up to the annulus and pumped 75 sxs. S.I.P. 300#.

RECEIVED  
MAR 16 2006  
KCC WICHITA

Remarks: WELL RE-NAMED HOOF UNIT 101. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

100  
**INVOICED**

DATE 3-17-06

INVOICE NO. 2006061297

Form CP-2/3

MAR 14 2006

IMPERIAL DRILLING

# 100F

9-10-25W  
NE NE SW

Contr. IMPERIAL DRLG

GRAHAM

County

E 2433 RB Comm.

Comp. 12-24-54

IP 3000 BOPD

BOMB POT

Tops	Depth	Datum
ANH	1995	438
HEEB	3669	-1236
TOR	3690	-1257
LANS	3702	-1269
TD	3955	-1522

Casing

8" 217 DST 3690-98/1 HR, 800' GAS, 175' MOC, BHP 1215#; DST 3784-11/45", 1700' FRE OIL BHP 1260#; DST 3790-45/1 HR, 3000' GAS 475' MOC, BHP 1260#; DST 3751-60/1 HR, 1100' FRE OIL, BHP 1260#; DST 3786-95/1 HR, 400' GSY MDY OIL, BHP 1290#; DST 3800-07/1 HR, 280' FRE OIL, BHP 1385#; DST 3841-52/1 HR, 60' GAS, 450' OC SW, BHP 1200#; DST 3860-71/48", GAS TO SURF 10", FLO IN 30", EST 43 BOPH BHP 1355#; DST 3880-92/1 HR, 2860' OIL, BHP 1260#; DST 3901-11/1 HR, HOOF POOL 125' V H OCM, BHP 1200#; PERF 24/3881-85: SWB 16 1/2 BOPH/4 HR; AGID 4000: FLO 40-46 BOPH/8 HR; PB 3876: 23/3865-69: FLO 40 BOPH 7 HR; AGID 5000: FLO 39 BOPH

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS