

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-08539-00-02  
Spot: E2W2NW Sec/Twnshp/Rge: 9-15S-13W  
4290 feet from S Section Line, 3960 feet from E Section Line  
Lease Name: A C ROGG A Well #: 1  
County: RUSSELL Total Vertical Depth: 3033 feet

Operator License No.: 5184  
Op Name: SHIELDS OIL PRODUCERS INC  
Address: 326 MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2977	0	50 SX CMT
SURF	15.5	340	0	300 SX CMT

\$ 98.57

Well Type: EOR UIC Docket No: E07570.1 Date/Time to Plug: 03/07/2006 8:30 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: MICHAEL A MCGLOCKLIN Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed  
Plugging  
Method:

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/07/2006 3:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 2500'.  
Pumped 100 sxs common with 3% cc and 350# hulls.  
Pulled up and let cement set up for 1 1/2 hours.  
Tagged cement.  
Pulled to 2200' and pumped 9 sxs gel. Max. P.S.I. 2000#.  
Pulled to 1750'. Max. P.S.I. 2000# with water.  
Pulled to 1200'. Pumped 4 sxs gel.  
POOH. Perforated at 800'.  
Ran tubing to 800' and circulated with 75 sxs 60/40 pozmix - 10% gel cement with 150# hulls.  
POOH.  
Tied onto casing and pumped 150 sxs cement with 150# hulls.  
Max. P.S.I. 500#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3014	3040		

RECEIVED  
MAR 16 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Care Morris  
(TECHNICIAN)

10  
**INVOICED**  
DATE 3-17-06  
SER. NO. 2006061296

MAR 14 2006

R. H. SHIELDS

#1

ROGG

9-15-13W  
CEL W2 NW

Contr.

RUSSELL

County

E 1819

Comm 5-18-38

Comp. 7-28-38

IP 588 BOPD

Tops	Depth	Datum
ANHY	760	
TOP	2675	
LANS	2978	
TD	3033	

Casing

10" 774  
8" 2283  
7" 2985

2 1/2 MCFG @ 2235-40

SO 2845

SO 2860-70

SO & G 2930-50

P & F 299 BO/4 hrs

P & F 88 BO/4 hrs

PAY 3000-33

A/10,000

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

133067