


15-193-00015-00-60

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Thomas County. Sec. 25 Twp. 7S Rge. (E) 31(W)
Location as "NE/CNW/SW" or footage from lines SE SE NW
Lease Owner Natural Gas and Oil Corporation
Lease Name Drew Well No. 1
Office Address 1009 Central Building, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed December 18, 1953 19
Application for plugging filed December 18, 1953 (orally) 19
Application for plugging approved December 18, 1953 19
Plugging commenced December 18, 1953 19
Plugging completed 11:30 PM December 18, 1953 19
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Box 326, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	284	8 5/8	284	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from total depth 4643 to 270 feet
Set plug and ran 15 sacks cement at 270 feet to 230 feet
Filled with heavy mud from 230 feet to 40 feet
Set plug at 40 feet and ran 10 sacks cement to cellar

12-29-1953

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Drilling Department of Natural Gas and Oil Corporation
Address 1009 Central Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Harold A. Burt, Regional Manager (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold A. Burt
1009 Central Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of December 19 53

Esther Insell

My commission expires May ;25, 1957

Notary Public.

PLUGGING
FILED DEC 25 1953 T-2 E 31W
BOOK PAGE 3 LINE 19

15-193-00015-00-00

DRILLER'S LOG

COMPANY: Natural Gas and Oil Corporation
and Republic Natural Gas Company

FARM: Drew No. 1, SE SE NW 25-7-31W
Thomas County, Kansas

CONTRACTOR: Drilling Department of Natural Gas
and Oil Corporation

COMMENCED: November 28, 1953

COMPLETED: December 18, 1953 (11:30 PM)

ELEVATION: 2978 RB

0	to	120	Sand and clay
120	to	245	Sand
245	to	1520	Shale and shells
1520	to	2120	Sand, shale and shells
2120	to	2325	Shale and shells
2325	to	2635	Shale and red bed
2635	to	2675	Anhydrite
2675	to	2940	Shale and red bed
2940	to	3060	Shale
3060	to	3185	shale and lime
3185	to	4065	Shale and lime
4065	to	4245	Lime
4245	to	4266	Lime and chert
4266	to	4540	Lime and shale
4540	to	4582	Shale
4582	to	4608	Shale and lime
4608	to	4642	Miss lime and chert
4642	to	4643	Miss
		4643	T. D. (RB)

Set 284 feet of 8 5/8" surface. Cemented with 265 sacks cement and 4 sacks calcium chloride.

TOPS: Anhydrite 2635 Lansing 4039
 Heebner 4002 Mississippi 4605
 Toronto 4026

DRILL STEM TESTS:

- #1 4118-60, open 1 hr, shut in 20 Min, weak blow, rec. 100 ft mud, FFP 35#, BHP 1180#.
- #2 4195-4245, open 45 min, shut in 15 min, weak blow 10 min, rec. 25 feet mud, BHP 700#.
- #3 4458-78, open 1 hr, shut in 20 min, weak blow 7 min, rec. 15 feet mud, IFP and FFP 0#, BHP 1040#.

Schlumberger run
DRY, PLUGGED AND ABANDONED

1/25/53 RCM

CERTIFICATE

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of the log of the Drew #1, SE SE NW Section 25-7S-31W, Thomas County, Kansas, as reflected by files of the Natural Gas and Oil Corporation.

Harold A. Burt
Harold A. Burt, Regional Mgr

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 28th day of December, 1953.

Esther Unsell
Esther Unsell, Notary Public

My commission expires May 25, 1957.

PLUGGING
 FILE SEC 25 T 2 R 31W
 BOOK PAGE 3 LINE 19