

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-193-20236-00-10

TYPE OR PRINT
 PLEASE FILL OUT COMPLETELY
 AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Rall #1

WELL NUMBER _____

SPOT LOCATION SE SE SE

SEC. 26 TWP. 7s RGE. 31w (E) OR (W)

COUNTY Thomas

DATE WELL COMPLETED _____

PLUGGING COMMENCED 11/1/83

PLUGGING COMPLETED 11/5/83

LEASE OPERATOR John Roy Evans

ADDRESS Box 385, Claflin, Ks. 67525

PHONE # () _____ OPERATORS LICENSE NO. _____

CHARACTER OF WELL _____
 (OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays

IS ACC-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 4370'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	413'	none
				4 1/2"	4369'	1508'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Ran plug to 4230', ran 4 sacks cement, sand to 4170' & 4 sacks cement. Shot pipe at 3410', 3013', 2720', 2488', 2241', 2007', 1728', & 1508'. Pulled 35 joints. Plugged well with 3 hulls, 40 gel, & 170 sacks 50/50 poz 6% gel 3% c.c. Plugging complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE No. 6050
 ADDRESS Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.


R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) R. Darrell Kelso

(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 15th DAY OF November, 1983

Irene Hoover
 NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

RECEIVED
 STATE CORPORATION COMMISSION
11-17-1983
 NOV 17 1983

FORM CP-4
 REVISED 06-83