

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-193-20140-00-00

LEASE NAME Harold Ball

WELL NUMBER 1

SPOT LOCATION 330' FNL & FEL (*)

SEC. 35 TWP. 7S RGE. 31 (X) or (W)

COUNTY Thomas

Date Well Completed 06-20-77

Plugging Commenced 11-25-83

Plugging Completed 11-25-83

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Gulf Oil Corporation

ADDRESS P. O. Box 12116 - Oklahoma City, OK 73157

PHONE # (405) 949-7000 OPERATORS LICENSE NO. 5816

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? 6

Is ACO-1 filed? unknown If not, is well log attached? yes

Producing formation L-KC "J" Depth to top 4247 bottom 4249 T.D. 4681

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Lansing - KC "J"	Oil	4247	4249	8 - 5/8"	417	-0-
				5 - 1/2"	4406	1983

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

(see back of form)

(*) C/NE NE NE Sec. 35

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Barlow Well Service License No. 6690
Address P. O. Box 868 - Great Bend, KS 67530

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Dorretta Moore (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION
02-09-1984
FEB 09 1984

(Signature) Dorretta Moore

(Address) (same as operator)

SUBSCRIBED AND SWORN TO before me this 6th day of February, 1984

CONSERVATION DIVISION
Wichita, Kansas

Patricia A. W. Underly
Notary Public

My Commission expires: 01-31-87

11/25/83: P & A. TD 4681', PBTD 4356', 5½" csg @4406' MIRU Barlow WSU. RIH w/2-3/8" OD tbg to 4353'. MIRU Howco & spot 50 sk Cl "A" cmt f/4353-3923'. POH & LD tbg. Fill well w/fr wtr. Take stretch on csg. Shot csg @2600', 2250', 1983'. Csg free @1983'. Spot 60 sk Cl A cmt f/1983-1784'. POH w/csg to 480'. Circ 140 sk Cl "A" cmt to sfc. POH w/csg. Top off well w/10 sk cmt. WOC. RIH w/SLM. TOC=103'. Top off csg w/Redimix. Cut csg off 6' BGL. Capped & ID'd well.

Restore loc. Last Well on Lease. Well P & A'd 11/25/83. State man, Carl Goodrow notified but not on location.