

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-179-20,946-00-00  
 LEASE NAME Scheetz

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1  
2,970 Ft. from S Section Line  
1,650 Ft. from E Section Line  
 SEC. 35 TWP. 7 RGE. 26 (X) or (W)  
 COUNTY Sheridan  
 Date Well Completed 7-20-89  
 Plugging Commenced 11-9-93  
 Plugging Completed 11-9-93

LEASE OPERATOR Shields Oil Producers, Inc.  
 ADDRESS Shields Bldg., Russell, KS. 67665  
 PHONE#(913) 483-3141 OPERATORS LICENSE NO. 5184

Character of Well Oil  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-9-93 (date)  
 by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3,940'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	297'	Cmtd. w/160 sax
				4 1/2"	3,859'	Cmtd. w/500 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Test 8 5/8" surface casing and held to 500#; pump down 4 1/2" casing w/25 sax 60-40 pozmix, 10% jel w/200# hulls; 7 sax jel, 100 sax 60-40 pozmix, 10% jel w/100# hulls. Maximum pressure 2000#, shut in pressure 1000#. Job completed 12 noon 11-9-93.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Oil Producers, Inc. License No. 5184

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman (Employee of Operator) or ~~Operator~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas


(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 93

Ruth Phillips

Notary Public

My Commission Expires: \_\_\_\_\_



RECEIVED  
 STATE CORPORATION COMMISS.  
 NOV 29 1993  
 NOV 29 1993  
 CONSERVATION DIVISION  
 Wichita, Kansas