

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County. Sec. 24 Twp. 7 Rge. 27 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NE

Lease Owner Sauvage & Dunn Drilling Co., Inc.

Lease Name Babcock Well No. 1

Office Address Oberlin, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed August 7 1955

Application for plugging filed August 7 1955

Application for plugging approved August 7 1955

Plugging commenced August 8 1955

Plugging completed August 8 1955


Reason for abandonment of well or producing formation _____

dry

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud thru drill pipe pulled pipe to 260 feet set plug mixed with 15 sx cement and 1/2 sx. hulls. Filled with heavy mud to 40 feet set 2nd plug with 10 sx, cement 1/2 sx hulls. Filled hole to bottom of cellar

Name of Plugging Contractor Sauvage & Dunn Drilling Co., Inc.
Address Oberlin, Kansas

STATE OF Kansas, COUNTY OF Decatur, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

Oberlin, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of August, 1955

My commission expires May 17, 1959

[Signature]
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 24 T 7 R 27 W
BOOK PAGE 141 LINE 37

AUG 10 1955
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

OPERATOR: SAUVAGE & DUNN DRLG. CO., INC.
 FARM NAME: BABCOCK
 WELL NO: ONE

LOCATION: NE NE NE Sec. 24-78-27W
 Sheridan County, Kansas

CONTRACTOR: SAUVAGE & DUNN DRLG. CO., INC.

CASING RECORD: 265 ft. 8 5/8"
 casing 165 sx cement

ROTARY COMMENCED: July 25, 1955
 ROTARY COMPLETED: August 7, 1955

Figures denote bottom of formations

surface casing	265
shale	800
shale	1705
shale & pyrite	1945
red bed w/pyrite	2200
red bed w/pyrite	
anhyd	2330
lime & shale	2580
shale w/ lime streaks	2680
shale, lime w/pyrite	2770
shale, shells, lime	2915
lime & shale	2960
shale & lime	3225
lime & shale	3345
lime & shale	3424
shale	3462
lime & shale	3495
shale & lime	3720
lime	3833
lime	3935
lime	4028
lime	4100
shale & lime	4223
shale & lime	4350
lime & shale	4435
shale & lime	4450
rotary total depth	4450

CERTIFICATE

STATE OF KANSAS)
) SS
 DECATUR COUNTY)

I hereby certify that the foregoing is, to the best of my knowledge and belief a true, full and correct drilling log as shown by the daily drilling reports in connection with the aforesaid well.

Arthur Sauvage
 For Sauvage & Dunn Drlg. Co., Inc.

Subscribed and sworn to before me, the undersigned, a Notary Public this 15th day of August, 1955

Opal Sauvage
 Notary Public

My Commission expires May 17, 1959

PLUGGING
 FILE NO. 24-7-27W
 BOOK PAGE 141 LINE 37

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 14 1955
 AUG 16 1955
 CONSERVATION DIVISION
 Wichita, Kansas