


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Sheridan County. Sec. 1 Twp. 7S Rge. 27 (85) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner Veeder Supply and Development Co.
Lease Name Leidig Well No. 1
Office Address Box 201, Cherryvale, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed Dec. 17, 1958 19
Application for plugging filed Dec. 17, 1958 19
Application for plugging approved Dec. 17, 1958 19
Plugging commenced Dec. 17, 1958 19
Plugging completed Dec. 18, 1958 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. B. Fabricus, Hill City, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4095 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200' w/	135 sacks

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 600 feet. Set plug with 20 sacks cement; filled hole with mud to 200 feet. Set second plug with 1/2 sack hulls, 20 sacks cement. Filled with mud to 40 feet. Set top plug with 1/2 sack hulls, 10 sacks cement. Cemented to bottom of cellar.

REC'D
STATE CORPORATION COMMISSION

DEC 29 1958
DEC 29 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Veeder Supply and Development Co.
Address Box 201, Cherryvale, Kansas

STATE OF Kansas, COUNTY OF Montgomery, ss.
C. H. Woods (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Woods

Cherryvale, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 22nd day of December, 19 58

Leo Lawson
Notary Public.

My commission expires July 11, 1960

PLUGGING
FILE SEC. 1 T 7 R 27 W
BOOK PAGE 9 LINE 24

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Veeder Supply and Development Co.,
Ira E. Sanditen, et al Farm Leidig No. 1 Depth 4095'
 Contractor Veeder Supply & Development Co. Pipe 200' 8 5/8" csg. w/135 sacks
 Location NW/4 NW/4 NW/4 Sec. 1 Twp. 7S Range 27W
 Commenced 12-7-58 Completed 12-18-58 County Sheridan State Kansas

Cellar	0	9	9
Native soil	9	40	31
Sand shale	40	170	130
Shale	170	200	30
Shale and sand	200	800	600
Shale and shells	800	1340	540
Shale and lime shells	1340	1590	250
Shale, shells	1590	1850	260
Shale	1850	1990	140
Shale w/sand	1990	2145	155
Shale, red bed	2145	2364	219
Anhydrite	2364	2399	35
Shale	2399	2412	13
Shale and shells	2412	2570	158
Shale w/lime streaks	2570	2875	305
Lime and shale	2875	3000	125
Shale w/lime streaks	3000	3138	138
Lime w/shale	3138	3200	62
Lime and shale	3200	3280	80
Lime w/shale breaks	3280	3340	69
Lime and shale	3340	3944	604
Lime	3944	4095	151
T. D.	4095		

D&A

AFFIDAVIT

STATE OF KANSAS)
Montgomery County) SS

C. H. Woods, of lawful age, being first duly sworn on oath, deposes and says:

THAT he has read the above drilling log covering the Leidig #1 well located in Section 1-7S-27W, Sheridan County, Kansas, and that the same is true and correct. Further affiant saith not.

THE VEEDER SUPPLY AND DEVELOPMENT CO.

By C. H. Woods
C. H. Woods

Subscribed and sworn to before me this 22nd day of December, 1958.

L. L. Lawson
Notary Public

My commission expires July 11, 1960.

STATE OF KANSAS
COMMISSION

DEC 29 1958
DEC 29 1958
CONSERVATION DIVISION

W ch PLUGGING
 FILE SEC. 1 T 7 R 27W
 BOOK PAGE 9 LINE 24