

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Sheridan County. Sec. 2 Twp. 7 S Rge. 27 XXW
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
100' East SW NE


Lease Owner F & M Oil Company
Lease Name SNIFFIN Well No. 1
Office Address 505 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date Well completed June 1, 1977
Application for plugging filed (verbally) June 1, 1977
Application for plugging approved (verbally) June 1, 1977
Plugging commenced June 1, 1977
Plugging completed June 1, 1977

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered.
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug at 1200' with 70 sx.
2nd plug at 240' with 20 sx.
3rd plug at 40' with 10 sx.

Plug was down at 12:30 a.m. 6-1-77.

JUN 15 1977

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Jack L. Partridge, Ass't. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of June, 1977

My commission expires _____

Kathy S. Goertz
Kathy S. Goertz, Notary Public.



CONTRACTOR'S WELL LOG

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: SNIFFIN #1
 LOCATION: 100' East SW NE Section 7-7S-27W,
 Sheridan County, Kansas
 SPUD DATE: 5-24-77
 COMPLETION DATE: 6-1-77

0	240	Clay & sand
240	1570	Shale
1570	2097	Shale & sand
2097	2157	Sand
2157	2374	Shale
2374	2408	Anhydrite
2408	2748	Shale & lime
2748	2957	Lime & shale
2957	3216	Shale & sand
3216	3339	Shale & lime
3339	3453	Lime & shale
3453	3598	Lime
3598	3795	Shale & lime
3795	3858	Lime & shale
3858	4100	Lime
	4100	Rotary Total Depth

Spud hole at 5:30 p.m. 5-24-77. Drilled 254' of 12 1/4" hole. Ran 6 jts. of 8-5/8" surface casing. Set at 253' K.B. Cemented with 190 sacks of cement, 3% CaCl, 2% gel. Plug was down at 10:00 p.m. 5-24-77.

T.D. 4100'. Set first plug at 1200' with 70 sacks, second plug at 240' with 20 sacks, third plug at 40' with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 12:30 a.m. 6-1-77. State plugger, Gilbert Balthazor.

SAMPLE TOPS:

Anhydrite 2374'
 B/Anhydrite 2408'

JUN 15 1977

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SNIFFIN #1, 100' East SW NE Section 7-7S-27W, Sheridan County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge
 Jack L. Partridge, Assistant Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 7th day of June, 1977.



Kathy S. Goertz
 Kathy S. Goertz, Notary Public