

9-18

6 041225

API NUMBER 15- 163-21,403 -00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW _____, SEC. 27, T 8 S, R 17 W/E

1620 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5134

Lease Name Bemis Well # 1-27

Operator: Graham Michaelis Corp

County Rooks 112.12

Name & Address Box 247

Well Total Depth 3450 feet

Wichita, Ks. 67201

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 256 w/180

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Russell, Ks.

Company to plug at: Hour: 10:00AM Day: 18 Month: Sept Year: 19 90

Plugging proposal received from Norman Rodie

(company name) Graham Michaelis (phone) _____

were: 4 1/2 casing set at 3447 w/200 sks cement: perfs at 3130.

Perf casing at 2275; perf base dakota at 750. Ordered 250 sks 65/35 poz 10% gel w/1/4 lb f.c. plus 5 sks hulls plus 10 sks gel.

Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 7:50PM Day: 18 Month: Sept Year: 19 90

ACTUAL PLUGGING REPORT R.I.H. w/free point to 2385. Cut off casing at 2275: Pulled

at 20' of 4 1/2 casing; pumped 12.5 bbls of gel followed w/25 sks cement, followed w/12.5 bbls

of gel, followed w/20 bbls/60 sks of cement: ^{Attempted to} pull casing: casing hung up on hole: comm

R. I . H. w/free point to 820, cut off casing. Pulled 2 joints of casing. Hooked up

cementrs and pumped 105 sks cement to circ cement at surf. Pulled casing. Hooked up to 8 5/8

s.p. and sq add. 60 sks cement. Max 500 lbs. S.I., 100 lbs.

Remarks: _____

INVOICED (did/did not) observe this plugging. If additional description is necessary, use BACK of this form.)

DATE 10-10-90

INV. NO. 29613

G.L.S.

Signed Dennis L. Hamel (TECHNICIAN)

RECEIVED OCT 8 1990 CON DIVIS WICHITA KANSAS 10-8-90