

4 050040

5-1

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5900

Operator: Lawbanco Drilling Inc.
Name & Address Main St.
Natoma, Kansas 67651
913-885-4676

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address _____

Company to plug at: Hour: 11:00AM Day: 1 Month: May Year: 1990

Plugging proposal received from Lawbanco Drilling Inc.

(company name) _____ (phone) _____

were: Order 400 sks 65/35 poz 8% gel and 700# hulls.

Plugging Proposal Received by Marvin Miller
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 6:45 PM Day: 1 Month: May Year: 1990

ACTUAL PLUGGING REPORT 8 5/8" set at 221' w/150 sks. Casing leak at 780'. Perforated at 1320'. Ran tubing to 2616' tubing would not go any deeper. Pumped 70 sks cement w/ 150# hulls. Pulled tubing to 1307. Pumped 130 sks cement w/250# hulls. Pulled all tubing. Pumped 100 sks cement w/100# hulls down 8 5/8". Max psi 500#. Shut in psi 200#. Pumped 100 sks cement w/200#. Hulls down 4 1/2". Max psi 400#. Shut in psi 200#.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / expect) observe this plugging.

DATE 5-16-90
INV. NO. 28159
5-1
JUL 11 1990

Signed Marvin Miller
(TECHNICIAN)
Marvin Miller